Unit 686 Removing and repairing eaves and verge finishings in the workplace

16 credits

Level: 2
UAN: D/600/7177

Unit aim:
This unit aims to provide you with the necessary skills and knowledge to:

- interpret information
- adopt safe and healthy working practices
- select materials, components and equipment
- remove and/or repair/replace existing eaves and verge finishings and background surfaces ready for new installation.

*PER – Portfolio evidence reference SO – Site observation OQ – Oral question WQ – Written question WT – Witness testimony
PS – Product supplementary PD – Professional discussion

Assessment criteria that are practical activities are highlighted in bold.

1. Interpret the given information relating to the work and resources when removing and repairing eaves and verge finishings.							
You must be able to:	*PER	SO	OQ	WQ	WT	PS	PD
1.1 **interpret and extract information from:**							
a. **drawings**							
b. **scales**							
c. **specifications**							
d. **schedules**							
e. **manufacturers' information**							
1.2 **comply with information and/or instructions derived from risk assessments and method statement**							

1.3 state the organisational procedures developed to report and rectify inappropriate information and unsuitable resources and how they are implemented							
1.4 describe different types of information, their source and how they are interpreted in relation to:							
a. drawings							
b. scales							
c. specifications							
d. schedules							
e. manufacturers' information							
f. regulations governing buildings.							

2. Know how to comply with relevant legislation and official guidance when removing and repairing eaves and verge finishings.							
You must be able to:	*PER	SO	OQ	WQ	WT	PS	PD
2.1 describe your responsibilities under current legislation and official guidance whilst working:							
a. in the workplace							
b. at height							
c. with tools and equipment							
d. with materials and substances							
e. with movement/storage of materials							
f. by manual handling							
g. by mechanical lifting							
h. near telephone lines and overhead power supplies							
2.2 describe the organisational security procedures for tools, equipment and personal belongings, in relation to:							
a. site							
b. workplace							
c. company							
d. operative							
2.3 state what the accident reporting procedures are and who is responsible for making reports.							

3. Maintain safe working practices when removing and repairing eaves and verge finishings.							
You must be able to:	*PER	SO	OQ	WQ	WT	PS	PD
3.1 **use Personal Protective Equipment (PPE), access equipment and handle asbestos cement materials (as applicable) safely to carry out the activity, in accordance with legislation and organisational requirements when removing and repairing eaves and verge finishings**							
3.2 explain why and when Personal Protective Equipment (PPE) should be used, relating to removing and repairing eaves and verge finishings, and the:							
a. types							
b. purpose							
c. limitations of each type							
3.3 state how emergencies should be responded to in accordance with organisational authorisation and personal skills when involved with:							
a. fires							
b. spillages							
c. injuries							
d. other task-related hazards.							

4. Select the required quantity and quality of resources for the methods of work to remove and repair eaves and verge finishings.							
You must be able to:	*PER	SO	OQ	WQ	WT	PS	PD
4.1 describe the characteristics, quality, uses, limitations and defects associated with the resources in relation to:							
a. timber							
b. tiles and slates							
c. sarking							
d. fixings							
e. fittings							
f. sand							
g. cement							
h. hand and/or powered tools and equipment							

4.2 **select resources associated with own work in relation to:**							
a. **materials**							
b. **components**							
c. **fixings**							
d. **tools**							
e. **equipment**							
4.3 state how the resources should be used correctly, how problems associated with the resources are reported and how the organisational procedures are used							
4.4 outline potential hazards associated with the resources and method of work, with particular emphasis on asbestos cement materials							
4.5 describe how to calculate:							
a. quantity							
b. length							
c. area							
d. wastage associated with the method/procedure to remove and repair eaves and verge finishings.							

5. Minimise the risk of damage to the work and surrounding area when removing and repairing eaves and verge finishings.							
You must be able to:	*PER	SO	OQ	WQ	WT	PS	PD
5.1 **protect the work and its surrounding area from damage**							
5.2 **minimise damage and maintain a clean work space**							
5.3 describe how to protect work from damage and the purpose of protection in relation to:							
a. general workplace activities							
b. other occupations							
c. adverse weather conditions							
5.4 **dispose of waste in accordance with legislation**							
5.5 state why the disposal of waste should be carried out in relation to the work.							

6. Complete the work within the allocated time when removing and repairing eaves and verge finishings.							
You must be able to:	*PER	SO	OQ	WQ	WT	PS	PD
6.1 **demonstrate completion of the work within the allocated time**							
6.2 state the purpose of the work programme and explain why deadlines should be kept in relation to:							
a. types of progress charts, timetables and estimated times							
b. organisational procedures for reporting circumstances which will affect the work programme.							

7. Comply with the given contract information to remove and repair eaves and verge finishings to the required specification.							
You must be able to:	*PER	SO	OQ	WQ	WT	PS	PD
7.1 **demonstrate the following work skills when removing and repairing eaves and verge finishings:**							
a. **measuring**							
b. **marking out**							
c. **removing**							
d. **replacing**							
e. **fitting**							
f. **positioning**							
g. **securing**							
7.2 **remove to contractor's working instructions:**							
a. **gutters and pipework**							
b. **fascias**							
c. **bargeboards**							
d. **soffits**							
e. **tiles/slates**							
f. **battens**							
g. **sarking**							
7.3 **repair/replace to contractor's working instructions:**							

a. **rafters and/or joist feet**							
b. **tile battens, sarking, tiles and slates.**							
c. **application of appropriate timber preservative**							
d. **roof pointing to verges**							
7.4 describe how to apply safe work practices, follow procedures, report problems and establish the authority needed to rectify them, to:							
a. remove existing gutters, fascias, snow guards, leaf traps, bargeboards, soffits, tiles and slates, asbestos cement materials							
b. repair feet of existing rafters and/or joists							
c. replace sarking and battens							
d. locate and remove telephone lines and overhead power supplies in accordance with organisational policy							
e. assess expansion and contraction across products							
f. assess compatibility across manufacturer's products							
g. use hand tools, power tools and equipment							
h. use access equipment							
7.5 **safely use and store hand tools, portable power tools and ancillary equipment**							
7.6 state the needs of other occupations and how to communicate within a team when removing and repairing eaves and verge finishings							
7.7 describe how to maintain the tools and equipment used when removing and repairing eaves and verge finishings.							

Unit 686 Removing and repairing eaves and verge finishings in the workplace

Declaration

I confirm that the evidence supplied for the above unit is authentic and a true representation of my own work. The work logged is my own work carried out during my normal work duties.

Candidate name:	
Candidate signature:	
Date:	

I confirm that this candidate has achieved all the requirements of this unit with the evidence listed. Assessment was conducted under the specified conditions and context, and is valid, authentic, reliable, current and sufficient.

Assessor name:	
Assessor signature:	
Date:	

IQA name:	
IQA signature:	
Date:	